RITE WAY FENCING INC.

October 20, 2026

RM OF BIG ARM
IMPERIAL SK **306-963-7787** **Email:** rm251reeve@icloud.com

ATTN: Sheldon

Re: **Proposed Supply & Install of Chain Link Fence & Gate – SPRING 2027 -** File: 26-593

In response to your price inquiry regarding the above project, based on information provided, we take pleasure in submitting the following quotation for your consideration.

Please have all underground lines clearly marked, RITE-WAY FENCING assumes no responsibility for unmarked sprinkler lines/heads or any other unmarked buried lines or objects. The customer will assume all liability for any damaged caused by directing RITE-WAY to dig in the immediate vicinity of any known utilities. HYDRO Vaccing of Post holes, if required, to be an additional charge.
Quotation is based on normal soil conditions and on a cleared fence line. Additional expenses for installation resulting from the existence of trees, brush, bedrock, boulders or marshy ground shall be charged and paid for as extras. **Staking / surveying of fence / property line by OWNER.**

Scope of proposed work: To supply labor, equipment and materials to approximately 1904 Lft of 6' high chain link fence with matching cantilever gate. All posts to be set in concrete footings - **9" x 42"** for line posts and **9" x 48"** for terminal posts. Strength of concrete to be 25 mpa Standard portland. Top of concrete footings to 2" to 3" below grade and topped off with spoil soil from post holes; remainder of spoil-soil to be spread evenly around posts and along fence line.

APPROX 1904 Lft of 6' high Chain link Fence with Cantilever Gate

List of materials, quantities & relevant spec's:
5 - 3-1/2" **o.d**. x 9' 6" SS 20 Terminal Posts c/w fittings
2 - 3-1/2" **o.d**. x 10' 6" Sch 40 Cantilever Support Posts c/w fittings
1 – 20' net opening x 7' BWO Single CANTILEVER Gate c/w Hardware & Rollers
1884 Lft of 6' high Fence: **2-3/8" o.d**. x 8' Line Posts, 1-5/8**" o.d**. Top Rail, 2" x 9 Ga - 72" Galv Chain link Mesh, 9 Ga Bottom wire and all required fittings for a complete job.

Our price for the above, SUPPLIED & INSTALLED is $58,992.00, plus Applicable Taxes.

Estimate valid for 30 days.

Deposit is required. **REMAINDER OF PAYMENT DUE UPON COMPLETION**. Thank you for the opportunity to quote on this project.

RITE-WAY FENCING (2000) INC
Cathy Young

Job Acceptance:
I _____ have agreed to the price as indicated above and would like Rite-way Fencing (2000) Inc to proceed with the installation.

_____ _____
Signature Date