FENCE QUOTATION

GEIGER'S FENCE ERECTORS LTD.

PHONE (306) 569-9382 | 146 6TH AVENUE EAST REGINA SK S4N 5A5 | www.geigersfence.com | info@geigersfence.com | FAX (306) 569-9385

TO	PROJECT	DATE
Sheldon Vance RM 251 Imperial, SK rm251reeve@icloud.com	Chain Link Fence Compound	26-Oct-26
		QUOTATION NO. **26-976**

WE ARE PLEASED TO SUBMIT OUR QUOTATION FOR THE FOLLOWING FENCE:

To supply and install 1,904ft of 6ft high all galvanized chain link fence including:

- 9 gauge galvanized mesh & bottom cable
- 1 5/8".079 top rail
- 2 3/8".079 line posts, 10ft apart
- 4 - 3 1/2".125 corner posts
- 1 - 20ft single cantilever gate
- 2 - 3 1/2"sch.40 cantilever gate posts
- 4 - 3 1/2" cantilever rollers
- 1 - 3 1/2".125 gate latch post
- All posts set in concrete
- All necessary fittings and hardware

$44,598.00 plus both taxes

A 3% processing fee will be applied to all Mastercard and Visa payments.
Price does not include privacy slats unless otherwise noted.
Please note: We require a clear fence line, with all trees, shrubs and obstructions removed prior to our arrival on site.

GST	TERMS	DELIVERY
EXTRA 5%	21 DAYS	**2027**
PST: EXTRA 6%	F.O.B.: JOB SITE	

ALL QUOTATIONS ARE BASED ON NORMAL SOIL CONDITIONS AND ON A CLEARED FENCE LINE. ADDITIONAL EXPENSES OF INSTALLATION RESULTING FROM THE EXISTENCE OF SLAG, TREES, BRUSH, BEDROCK, BOULDERS, PAVEMENT, SIDEWALK, FOUNDATIONS OR MARSHY GROUND, SHALL BE CHARGED AND PAID FOR AS EXTRAS.

THE PURCHASER AGREES TO INDEMNIFY THE SELLER AGAINST ANY CLAIMS ARISING FROM DAMAGE CAUSED TO UNDERGROUND CABLES, CONDUITS OR PIPES OF ANY KIND IN THE ERECTION OF FENCE UNLESS THE PURCHASER HAS INFORMED THE SELLER OF THE LOCATION. LOCATION INFORMATION IS AVAILABLE ON REQUEST FROM PUBLIC UTILITIES.

ALL PRICES ARE SUBJECT TO CHANGE

THANK YOU,

TOM NICHOLSON

CUSTOMER'S ACCEPTANCE