



**ESTIMATE PROVIDED TO:** RM OF BIG ARM  
**LOCATION:** IMPERIAL, SK  
**PHONE:** (306) 963 - 7787  
**E-MAIL:** rm251reeve@icloud.com  
**ESTIMATE FOR:** 60 x 80/100 - 18' STICK FRAME BUILDING  
**ESTIMATE DATE:** FEBRUARY 25, 2026  
**ESTIMATE PROVIDED BY:** LUKE UNGER

---

**ESTIMATE INCLUDES:**

- Engineered blueprints for foundation and structural scopes
- Building envelope energy modelling and code review for permits
- Treated 2 x 8 bottom plates, sill gasket, anchor bolts
- 2 x 8 wall construction 16" on center, with mid-span blocking @ 4' o/c
- 7/16" OSB wall sheathing with house wrap
- One eave wall to have 2-layers of 5/8" Type-X on each side of the walls, fire taped, to create a 2-hr fire rating
- Engineered commercial truss 4' on center with 2' overhang, attached with engineered fasteners
- 2 x 6 spruce #2 or better roof strapping 2' on center
- Vented metal soffit and fascia
- 29-gauge Tuff-Rib colored roof metal with ridge venting
- 29-gauge Tuff-Rib colored wall metal and trims
- (3) 36" commercial steel, insulated walk door with lock set
- (2) 24 x 16'10" inward operating Findoors, with electric operator and transmitters, LVL headers, colored exterior finish
- Interior finish
  - R28 wall insulation
  - R50 attic insulation
  - CGSB poly vapor barrier with acoustical caulking and tuck tape
  - 1 x 4 spruce wall strapping 2' on center
  - 29-gauge colored Tuff-rib wall and ceiling finish
- Concrete
  - Place/pack 6" base layer (customer supplied)
  - Engineered steel screw piles at 10' on center
  - 32" insulated grade beam, void form
  - Entire slab to have 2" korolite styro underneath with 5/8" commercial grade heat lines @ 12" o/c, manifold



- 6" concrete slab with rebar at 16" on center
- Machine finished with expansion lines cut
- 40' commercial u-drain system with a 24" sump pit and checkerplate lid
- Silicote spec sealer
- (4) 6" steel bollards with concrete in-fill, painted
- Minimum 30 MPA
- Labor included to construct building, install findoors, finish interior, blow in attic, prep/place/finish all concrete, travel/mileage
- Material delivery and disposal, porta potty

**TOTAL MATERIAL & LABOR PACKAGE**

**60 x 100 – 18'**

**\$ 553,155.00**

**60 x 80 – 18'**

**\$ 469,620.00**

**Plus Applicable Taxes**

**ESTIMATE DOES NOT INCLUDE:**

- Permits, construction insurance
- Site preparation, grading, leveling, excavation
- Gravel/ base product below all concrete
- Plumbing, heating and electrical
- Utility locates, Survey
- Winter heating, extra drilling costs due to rocks, frost, etc.

**NOTE: BUILDING SITE REQUIREMENTS**

- **A MINIMUM OF 10' LEVEL GRADE AROUND BUILDING IS REQUIRED**
- **A MINIMUM OF 20' WORKING SPACE AROUND BUILDING SITE REQUIRED**
- **ADDITIONAL LABOR CHARGES WILL APPLY AT CONTRACTOR DISCRETION IF SITE CONDITIONS NOT APPROPRIATELY MET**

**CONTRACT**

**Personal Information:**

**Customer Name:** \_\_\_\_\_

**Business Name:** \_\_\_\_\_

**Mailing Address:** \_\_\_\_\_

**Job Site Legal Land Location:** \_\_\_\_\_

**Phone Number:** \_\_\_\_\_ **Fax Number:** \_\_\_\_\_

**Cellular Number:** \_\_\_\_\_

**Email Address:** \_\_\_\_\_

This estimate is furnished for 7-day acceptance only from February 25, 2026. Clerical errors and errors of omission subject to correction. Nothing whatsoever not specifically listed will be furnished under this estimated amount.

Estimate provided is quoted as a complete project in substance.

Any reduction in the project must be explicitly and precisely agreed to at that time. Work or product initially included in this quote will be credited only as quoted at the discretion of Zak's Building Group management, not at customer discretion or retail levels. Reductions in this project in any form will be verified in writing to the customer, otherwise the contract is binding in its entirety.

Any extra charges not included in this quotation, whether agreed to verbally or in writing, will be billed direct and are over and above the amount quoted herein. Any work undertaken over and above listed specifications which will result in additional charges should only be executed upon an Additional Work Authorization form being completed and endorsed by the customer.

Account and contract subject to credit approval. Upon approval terms of this contract are:

- 1) 10% due upon acceptance of contract.
- 2) Monthly billing of costs as accumulated at each month end to be provided to customer not later than the 7<sup>th</sup> of the month following the month end.
- 3) Payment for the total amount invoiced to be due no later than the 15<sup>th</sup> day of the month following the invoice date (less 10% holdback if applicable). ALL LATE PAYMENTS WILL BE SUBJECT TO 1% SERVICE CHARGE, COMPOUNDED MONTHLY.

IN THE EVENT ARRANGEMENTS HAVE NOT BEEN MADE FOR PAYMENT, WORK ON PROJECT WILL STOP AND A BUILDER'S LIEN WILL BE REGISTERED ON THE SAID PROPERTY.

- 4) Zak's Building Group carries a commercial liability and insurance package with Programmed Insurance Brokers Inc. However, construction insurance is the responsibility of RM of Big Arm.

**The specifications and conditions and pricing listed herein are satisfactory and by our / my signature(s) hereon, we authorize Zak's Building Group to perform the project as detailed herein.**

\_\_\_\_\_  
**Customer**

\_\_\_\_\_  
**Zak's Authorized Representative**

\_\_\_\_\_  
**Customer**

\_\_\_\_\_  
**Date**

