



Sales Contact Boyd Waldner (403) 836-0709 boyd.w@integritybuilt.com	Customer R.M. 251 - Sheldon Vance (306) 963-7787 rm251reeve@icloud.com
---	--

Quote Date: 2026-01-16
Expires On: 2026-01-30

Building Description - Davidson, Saskatchewan, Canada	Quote: PQ-85464-1
--	--------------------------

Commercial Shop

- Normal Occupancy Classification
- **Engineered Structural Blueprints and Schedules**

Shop 48' x 100' x 20'

- 4' O/C engineered trusses
- All Eave Walls Post Spacing are: 4 Feet O/C load bearing posts
- 2' O/C wall and roof strapping
- Structure Type: Gable
- Exterior Metal: Premium 29 gauge Hi-Tensile FC36 profile metal including a 3/4" rib
- Standard Ridge Cap
- Storm Bracket
- Full Insulation
 - R28 Wall Insulation
 - 2"x4" strapping @ 2' O/C
 - R50 Ceiling Insulation
 - 6mm CGSB Vapor Barrier
 - Full Insulation Premium 29 gauge Hi-Tensile FC36 profile metal including a 3/4" rib

Components

Shop

Posts

Load Bearing	Precast Concrete pier Foundation, 4 Ply 2x8 SPF Laminated Posts with Integrity Post Disc (Foundation Depth designed to 6' below final Grade / Top of Post Height designed to 21'6" above Final Grade)
2	Precast Concrete pier Foundation, 4 Ply 2x8 SPF Laminated Posts with Integrity Post Disc (Foundation Depth designed to 6' below final Grade / Top of Post Height designed to 21'6" above Final Grade) Posts needed for the 24'x18' Overhead Door #1 door

**Sales Contact**

Boyd Waldner
(403) 836-0709
boyd.w@integritybuilt.com

Customer

R.M. 251 - Sheldon Vance
(306) 963-7787
rm251reeve@icloud.com

Components

- 2 Precast Concrete pier Foundation, 4 Ply 2x8 SPF Laminated Posts with Integrity Post Disc (Foundation Depth designed to 6' below final Grade / Top of Post Height designed to 21'6" above Final Grade)
Posts needed for the 24'x18' Overhead Door #2 door

Entry Doors

- 2 3' White Steel Entry Door, Outswing, Wall Stop

Overhead Doors

- 2 24'x18' White Commercial Overhead Door, Operator, 6 Window Inserts Per Door

Windows

- 5 3x3 Fixed Window

Miscellaneous

- 4 Metal Gable Vents
1 Fire Block Running Width Of Building
3 Smoke Damper
208 Feet of Knight Eavestrough
4 Knight Eavestrough Downspouts
2 Attic Hatches

Total: \$293,783.00 + tax

Includes Labour/Materials/Freight

Costs related to site preparation, rock required for post foundation, porta potties and waste disposal are the sole responsibility of the Purchaser and are not included unless otherwise specified above.

Warranty

- 5 year standard workmanship
- 40 year on metal cladding paint

**Sales Contact**

Boyd Waldner
(403) 836-0709
boyd.w@integritybuilt.com

Customer

R.M. 251 - Sheldon Vance
(306) 963-7787
rm251reeve@icloud.com

-
- 1-year limited windows, entry door, and large door
 - Lifetime warranty on precast concrete pier foundations

**DISCOVER
THE
INTEGRITY
DIFFERENCE**

**DuraColumn
Storm Bracket
Frost Shield
Skirt Wall Panel
Insulation Package**



WHY CHOOSE INTEGRITY?

**5 YEAR WORKMANSHIP WARRANTY
CERTIFIED INTEGRITY CREWS
ENGINEERED BUILDINGS
COR SAFETY CERTIFIED
NFBA MEMBER**